

Fiscal Year 2026-2027 Stormwater Project List

Location	Summary
Maple Row Blvd Storm	Install storm infrastructure in ROW funded by ARPA WIIP
William Shy	Install designed storm infrastructure funded by ARPA WIIP
Stop Thirty Pipe Upgrades	Upsize 4 pipes along Stop Thirty as part of paving project
118-122 Sunset Place	Drainage area investigation and backyard flooding downstream
Stream Restoration - Autumn Creek	Design, obtain permits, and restore historical stream sections
326 Raintree	Design and construct improvements to manage roadway drainage
114 Woodvale	Design and construct improvements to manage upstream system drainage
106 Spruce/ Forest Meadows Ct	Intercept spring and address run-on to public street
Saundersville Road	Evaluate, redirect and/or convey spring in the roadway
Cherokee Culvert	Obtain necessary right of way/easements and construct new, upsized culvert to replace existing
Nathan Forest Court	Add catch basin and 16' of pipe to tie-in to existing box
116 Savely	Replace dilapidated 24" CMP under road
99 Anchor	Reshape and stabilize 300' ditch line, replace dilapidated CMP under Anchor
Stream Restoration - Indian Ridge	Design & obtain permits to restore historical stream sections
Stream Restoration - Glenn Oak	Design & obtain permits to restore historical stream sections
101-105 Brookside	Replace 100' curb
119 Lakeside Park	Reshape and stabilize 100' of roadside ditch line
175 Rebecca	Reshape and stabilize 60' ditch line
203 Township	Jet pipe, realigns outlet, improve outfall, reshape and stabilize ditch line
Inlet Drive Ditch Restoration	Reshape and stabilize roadside ditch lines along both sides of street
Hickory Heights Ditch Restoration	Reshape and stabilize ditch lines along Hickory Heights
Maureen Ditch Restoration	Restore roadside drainage
Glen Hill Ditch Restoration	Restore roadside drainage
Cumberland Drive Ditch Restoration	Restore roadside drainage
111 Trousdale	Jet 20' pipe from street to headwall, reshape and stabilize 50' ditch line
247 Crooked Creek	Reshape and stabilize ditch line
105 Candle Wood Dr	Jet two pipes under Candle Wood, reshape and stabilize 500' ditch
135 Ashland Point	Reconstruct curb line to control roadway runoff
Imperial Road Pipe/Box	Cut road, remove old box, and tie-in new pipe